Smart Grid Project in Dubai


IoT in Dubai)

June, 2017

KEPCO

Huyoung Lee, pcmker3@kepco.co.kr

1. KEPCO in Brief



2-1. Cases of KEPCO Projects

Jeju Smart Grid Test-bed ('09~'13)

- 168 companies in 12 consortiums
- Tested in 5 areas, 2 S/S, 4 D/L, 3,000 customers
 - ⇒ Developed 45 BMs (DR management, AMI, EMS, EVC, ESS, etc.)



Jeju Gapa Island Microgrid ('11~'12)

- The world's first Microgrid Operation System Model
 - ⇒ Applied to deploy Energy Independent Island BM
- Replaced 3 Diesel Generators→Wind+Solar+ESS+EV+AMI+DAS



Advanced Metering Infrastructure(AMI) ('13~'20)

Installations in 2 stages: '13~'16(49%), '17~'20(100%)

	Stage 1			Stage 2				Total	
	'13	′14	'15	'16	'17	'18	'19	'20	Total
AMI Installed (10,000units)	200	230	250	257.5	250	250	330	364	2,194

Smart services(AOS, Power Planner) provided to customers

Power Planner

2-2. Cases of KEPCO Projects

EV Charging Infrastructure ('09~'16)

- EVC SPC Established('15) to build 3,660 chargers ('15~'18)
- Shorter distance between stations : '15(100km) → '16(30km)



Star-Network

Frequency Regulation(FR) ESS ('14~'17)

- Installation(500MWh): 236MWh(~'15), 140MWh('16), 124MWh('17)
- Replaced FR service(coal-fired power plant) with ESS
 - ⇒ 95% generation→100% : power purchasing costs(USD 120Mil./yr) saved



Nation-wide SG Station Installation ('13~'16)

Installed SG Stations (R/E+ESS+AMI+BAS+TOC) in 114 KEPCO offices

No. of Installed Offices	Reduced Peak	Reduced Elec. Consumption	Reduced CO ₂
114	4MW↓	10GWh↓	4,700tCO ₂ ↓



3-1. Overview of SG Station Pilot Project in Dubai

- Objective: To establish an expandable and sustainable Smart City model
- Duration: 2015.10 ~ 2017. 6
- **○** Target: Energy Saving 10%, Peak Cutting 8%, Reducing CO2 Emission 10%
- Obevice: PV 200kWp, BESS 540kWh, AMI, Smart Sensors, WT 9kW, TOC




3-2. Concept of the SGS Pilot Project in Dubai

- Smart Town Model for various types of buildings was applied such as Smart Office, Smart Building, and Smart Factory.
 - Small SG Station models integrated into one system (TOC)
- Self-sufficient sustainable energy supply system against future fossil fuels exhaustion was demonstrated using renewable energy and Micro Grid System by SG stations
 - Smart Office 20%, Smart Building 15%, Smart Factory 10%

Building	PV	ESS	PCS	WT	System
A, B, C	40 kW	45 kWh	120 kW	3 * 3 kW	SGS 1
D, E	40 kW	90 kWh	120 kW	-	SGS 2
C#1, C#2	120 kW	365 kWh	400 kW	-	SGS 3
Total	200 kW	500 kWh	640 kW	9 kW	TOC (Smart Town)

3-3. SGS Operation System (Main - Layout)



Pictures














3-4. SGS Operation System (Smart Town)



3-5. SGS Operation System (Control)



3-6. Function of SG Station S/W

Power Generation and Usage Monitoring as a real time

Each Building Power Usage, Each Floor Power Usage, Outlet, PV, ESS, Wind Turbine etc.

Analysis and Statistics

Power supply by PV, battery and power usage, etc.

Forecast of Power supply

• Forecast of electricity usage for demand by the artificial intelligent technique

Remote Control Equipment

PCS, VSD, Smart Light, Outlet, Air Conditioning Equipment, etc.

Operation Automatization


PV Generation, ESS charging/discharging control, Outlet

Fault Diagnosis Management

PV, ESS, Smart penal, Outlet, Light, etc.

4-1. Smart City Model for utility oriented

Smart City Model



Steps to Smart City



4-2. Lessons learned

■ Smart Grid with Building EMS

● IOT with Building EMS

SGS & DSM resources

● SGS & Grid operation efficiency

